

OFFICE OF THE PRINCIPAL
WOMEN'S TRAINING COLLEGE
NORTH GANDHI MAIDAN
PATNA UNIVERSITY, PATNA 800001
Website: wtcpu.org.in

EMERGENT NOTICE INVITING QUOTATION

Quotation No: 04/Ntc/2025

Date: 12.09.2025

NAME OF WORK: REPAIR AND RENOVATION OF CONFERENCE HALL , WOMEN'S TRAINING COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition , please visit the office of the undersigned on any working days from 10 30 A M to 5 00 P. M. or website of College

Designation of officer inviting quotation	Principal, Women's Training College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Women's Training College ,Patna up to 3 00 p.m. on 19.09.2025.
Place, Time & Date of opening quotation	Office of the Principal Women's Training College, Patna at 3.30 p.m. on 19.09.2025.

PREScribed FORMAT

PART A: REPAIR AND RENOVATION OF CONFERENCE HALL &							
PART B: REPAIR AND PAINTING OF HOME SCIENCE LAB							
S N	Code	Description	Quantity		Unit	Rate	Amount
	No					(Rs)	
1	15.5 6.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	67	Sqm	Sqm		
2	A.R.	Providing and fixing 1st quality ceramic glazed wall tiles of big size (300x600mm) confirming to IS: 15622 (Thickness to be specified by the manufacturer) of approved make in all colours, shades as approved by the engineer-in-charge in skirting, risers of steps and dados over 12 mm thick cement bed of cement mortar 1:3 and jointing with grey cement slurry @ 3.3 kg per sqm including pointing in white cement mixed with pigments of matching shade complete .	67	Sqm	Sqm		
3	14.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement :4 fine Sand)	11	Sqm	Sqm		
4	13.8 0.	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repari scratches etc. complete.	164	Sqm	Sqm		
5	P.M. R.	Providing and fixing wall papers of approved quality, as per direction of Engineer-in-charge.	520	Sft	Sft		

P.147
58/9/25

S N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
6	13.8 0 A.2	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	127	Sqm	Sqm		
7	13.4 6.1	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	127	Sqm	Sqm		
8	2.35 .1.	Supplying chemical emulsion in sealed containers including delivery as specified Chlorpyrifos/Lindone emulsifiable concentrate of 20%	2	Litre	Litre		
9	13.9 3.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	51	Sqm	Sqm		
10		Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / aneling,C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :					
a	21.1 .1.1	For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	49	Kg	Kg		
b	21.1 .2.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron)	55	Kg	Kg		
11	21.3 .2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 5.50 mm thickness(weight not less than 12.50 kg/sqm	13	Sqm	Sqm		
12	9.10 0.2	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:100 mm	20	No	Each		
13	9.46.	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete:25 mm dia metre	15	m	m		

P.1644
08/02/25

S N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs)	
14		Providing and fixing vertical blinds of Vista Brand 100 mm lovers with all accessories and componenets of approved quality as per direction of engineer in charge.	140	Sft	Sft		
15		Carraige of materials : Sone sand from Koelwar, 45 Km distance of surface road.	2	Cum	Cum		
16		Price difference of materials for Patna urban area: Ordinary Portland cement.	8	Bag	Bag		
17		Reserved price for any other un seen work.	1	L.S.	L.S.		
TOTAL (PART A+B)							
PART C: DEVELOPMENT OF LAND AT NORTHERN SIDE OF SEMINAR HALL AND HOME SCIENCE LAB							
1	2.29	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1 5 m	77	Sqm	100 Sqm		
2	2.8	Earth work in excavation in foundation trenches or drains(not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m . including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	12	Cum	Cum		
3	2.21 8.	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.	6	Cum	Cum		
4	11.7 2.	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,	77	Sqm	Sqm		
5	4.1.2	Providing and laying in position cement concrete of specified grade exluding the cost of centring and shuttering-all work upto plinth level.1:1.5:3(1 Cement: 1:5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	8	Cum	Cum		
6	6.18. 4A	Half brick masonry with bricks of class designation 100A in foundations and plinth in : Cement mortar 1:4 (1 cement: 4 coarse send)	18	Sqm	Sqm		
7	13.1 8.	15 mm cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall.	15	Sqm	Sqm		
8	S.O.R	Carriage of materials					
a		Designation 100 A bricks from 8 Km distance of surface road with an additional lead of 1 Km lead of kutcha road.	3500	No	%0 No		
b		Stone aggregate from Manpur, Gaya 100 km distance	7	Cum	Cum		
c		Sone sand from Koelwar, 45 Km distance of surface road.	5	Cum	Cum		
d		Local sand from 3 Km distance of surface road.	7	Cum	Cum		

PKA
08/02/25

S N	Code	Description	Quantity		Unit	Rate	Amount
	No					(Rs)	
9	S O R	Price difference of materials for Patna urban area					
a		Cement	77	Bag	Bag		
b		Designation 100 A bricks	3500	No	%0No		
10		Reserved price for any other un seen work.	1	L S	L S		
TOTAL (PART C)							
TOTAL (PART A+B+C)							

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Women's Training College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, Women's Training College, Patna @ 2% i.e.Rs.7,800/- is essentialy required with quotations Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 2 month after receiving work order.
- 3 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 4 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs. 1,00,000 and under.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 The undersignd reserve the right to accept or reject any or all the quotations without assigning any reason.
- 7 All disputes, what so ever shall be reffered to the sole arbitration of the Principal, Women's Training College, Patna and her decision shall be final and binding on the agency.

H. Khan
08/09/2025
PRINCIPAL
WOMEN'S TRAINING COLLEGE
PATNA

PRINCIPAL
WOMEN'S TRAINING COLLEGE
PATNA

P. Khan
08/09/25