

OFFICE OF THE PRINCIPAL
WOMEN'S TRAINING COLLEGE
NORTH GANDHI MAIDAN
PATNA UNIVERSITY, PATNA 800001
Website: wtcpu.org.in

EMERGENT NOTICE INVITING QUOTATION

Quotation No: 03/12/2025

Date: 12.09.2025

NAME OF WORK: REPAIR AND RE FLOORING OF COMPUTER LAB , WOMEN'S TRAINING COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition , please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, Women's Training College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Women's Training College, Patna up to 3 00 p.m. on 19 09 2025.
Place, Time & Date of opening quotation	Office of the Principal, Women's Training College, Patna at 3 30 p.m. on 19 09 2025.

PRESCRIBED FORMAT

S.N	Code	Description	Quantity		Unit	Rate	Amount
	No					(Rs)	
1	OL71	Providing skilled labour for chisseling existing cement concrete flooring, for propesd re flooring work, as per direction of Engineer-in-charge.	1	Lab/ Day	Lab/ Day		
2	4.1.2.	Providing and laying in position cement concrete of specified grade exluding the cost of centring and shuttering-all work upto plinth level. 1:1.5:3(1 Cement :1.5.coarse sand:3 graded stone aggregate 20 mm nominal size	1.5	Cum	Cum		
3	14.1.1	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	13	Sqm	Sqm		
4	15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster includingdisposalof rubbish to the dumping ground within 50 metres lead	4	Sqm	Sqm		
5	11.4.1.2.	Providing and laying vitrified floor tiles in different sizes {thickness to be specified by the manufactruer) with water absorption's less than 0.08% an conforming to IS : 15622 of approved make in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joint with white cement and matching pigments etc., complete.Size of Tile 60x60 cm	29	Sqm	Sqm		
6	11.4.6.2	Providing and laying Vitrified tiles in different sizes (thickness to be specified bymanufacturer), withwater absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600 x 600 mm.	4	Sqm	Sqm		

P.K. Jaiswal
28/09/25

S.N	Code No	Description	Quantity		Unit	Rate	Amount
						(Rs.)	
7	13.80	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repari scratches etc. complete.	101	Sqm	Sqm		
8	13.80 A.2	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	114	Sqm	Sqm		
9	13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade :New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	114	Sqm	Sqm		
10	2.35.1	Supplying chemical emulsion in sealed containers including delivery as specified Chlorpyriphos/Lindone emulsifiable concentrate of 20%	1	Litre	Litre		
11	13.93.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	15	Sqm	Sqm		
12	9.46	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete 25 mm dia metre	5	m	m		
13	S.O.R	Carraige of materials : Sone sand from Koelwar, 45 Km distance of surface road.	2	Cum	Cum		
14	S.O.R	Price difference of materials for Patna urban area: Ordinary Portland cement.	20	Bag	Bag		
15	o111	Providing carpentor for reducing height of door for proposed re flooring work, as per direction of Engineer-in-charge.	1	Lab/Day	Lab/Day		
16		Reserved price for any other un seen work.	1	L.S.	L.S.		
TOTAL							

Terms and conditions:

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, Women's Training College, Patna or N.S.C./ Time Deposit of Post Office, duly pledged in the name of Principal, Women's Training College, Patna @ 2% i.e.Rs.2,000/- is essentilaly required with quotations. Remaining amount of Security Deposits. @ 8% of bill amount will be deducted from bill.
- 2 Work must be completed within 1 month after receiving work order
- 3 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S will be considered
- 4 Any working agency of Works Department, Patna University, Patna will also be considered for the works of Rs 1,00,000 and under.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 The undersignd reserve the right to accept or reject any or all the quotations without assigning any reason.
- 7 All disputes, what so ever shall be reffered to the sole arbitration of the Principal, Women's Training College, Patna and her decision shall be final and binding on the agency.

H. J. Ray
13/8/2025
PRINCIPAL

WOMEN'S TRAINING COLLEGE
PATNA

PRINCIPAL
WOMEN'S TRAINING COLLEGE
PATNA